

Somb

Gaslow International Ltd Castle Business Park Pavilion Way Loughborough Leicestershire LE11 5GW Tel: 0845 4000 600 email: sales@gaslow.co.uk web: www.gaslowdirect.com

USA Patent No 5780711 Italian Patent No 32246/BE/2003 UK Patent No 2301895 European Application 2187155 Regd design GB2038217 and GB2038218 Publication Date: Jan 2015

We reserve the right to change specifications without notice.

The Safest, Most Reliable Refillable Cylinder Range in Europe.....







Gas Systems for LPG

Gaslow Refillable Cylinders

Why struggle connecting, lifting and carrying heavy gas bottles and then pay 50% more for the gas than you have to?BECAUSE YOU ALWAYS HAD TO!

Then when you travel to Europe and you run out of gas, it becomes a nightmare as you cannot exchange your empty cylinder for a full one....BECAUSE THAT'S THE WAY IT IS!

NOT ANY MORE....Fit a Gaslow refillable!

Available from and simply installed by your local dealer, you can just pull up at one of the thousands of Autogas Service Stations throughout the UK and Europe and fill up just like your car! If you have a twin cylinder system, not only will it fill up the empty but top up your nearly full one at the same time you simply pay for what you use.

Try the system with one cylinder - using your standard cylinder with it. You can easily add a second Gaslow Refillable at any time as it needs no installation. When you come to replace your Van you have the simple option of taking the whole system with you!

Why has Gaslow upgraded to R67?

Well, gas systems installed into Caravans and Motorhomes have to respect the European Standard EN1949. When we pioneered our refillables back in 2005 they were produced to the TPED standard, which covers normal Calor type exchangeable cylinders, but we added the 80% shut-off filler valve. This cylinder was accepted by the UKLPG provided it is fixed and remains in-situ for filling and the filler is not directly connected to the cylinder.

However, it has now been successfully argued by one European country that a cylinder produced to TPED should NOT be filled at Autogas Stations even if it meets the UKLPG advice 026.

This may not directly affect the UK market at present but this obviously creates doubt and we need the EN standard to recognise refillable cylinders and clarify to which standard they should be produced. Until then, and, considering the argument, we believe the only way to future proof our refillables and conform to EN1949:2011+A1, which was updated in February 2013, is to treat the cylinder as a tank and, at the very minimum, produce them to the more stringent R67 tank standard.



Gaslow Refillable Cylinders

Introducing the Safest, Most Reliable Refillable Cylinder Range in Europe.....

. Because ONLY Gaslow offers three cylinders that meet the more stringent R67 tank standard which includes a Bonfire Test.

Unique safety features that ONLY R67 Gaslow refillables give:

- Built-in Excess Flow Valve which prevents full flow of gas if the regulator hose ruptures.
- The special micro-design filter prevents any liquid gas passing through the valve as it vaporises any liquid during normal use – this feature is now required in the new EN standard.
- Internal brass filter which helps prevent impurities contaminating the regulator and gas system.
- Improved, mechanically accurate contents gauge with upgradeable remote indicator.


.....INTRODUCING THE

R67

2

At last!....refilling is as easy as filling your car

With his Gaslow Refillable System installed, caravan journalist, Andrew Ditton discovers that refilling a gas cylinder is no more difficult than filling a car with petrol



Photographs of Filling station by kind permission of Andrew Ditton and "The Caravan Magazine"

Gaslow Refillable Cylinders

Refillable R67 Cylinders with level gauge 🔒 Specially designed to fit all caravans, motorhomes and campervans. The R67 approved cylinders have a 10 year warranty on the complete system which includes the 01-4011-67 11Kg cylinder special Multivalve which automatically shuts off the gas 01-4011-67-2 11Kg cylinder 2 when 80% capacity is reached - preventing dangerous overfilling. For complete safety, an excess flow valve prevents full flow of gas if the hose ruptures plus an 01-4006-67 6Kg cylinder Internal filter which protects the regulator and gas system 01-4006-67-2 6Kg cylinder 2 from impurities. In addition, we have a built-in SIGN overpressure safety device and a mechanically accurate contents gauge which can be upgraded to give remote 01-4003-67 2.7Kg cylinder reading of gas contents inside the vehicle. 01-4003-67-2 2.7Kg cylinder 2 11Kg cylinders carry 21 litres (80%). Height: 580 x 304mm diameter. Empty cylinder weight: 12.4Kg approx. Direct Fill Cylinders CASE 6Kg cylinders carry 11.5 litres (80%). Height: 492 x 01-4011-67-D 11Kg cylinder 246mm diameter. Empty cylinder weight: 8.1Kg approx m-1 6Kg cylinder 01-4006-67-D 2.7Kg cylinders carry 4.9 litres (80%). Height: 310 x 01-4003-67-D 2.7Kg cylinder 202mm diameter. Empty cylinder weight: 5.0Kg approx UK Autogas Bayonet Filling Kits in white or black finish Filling Kits together with screws for mounting on the side of your caravan or motorhome. Connection to the cylinder(s) is 01-4100 1.5m Kit - WHITE with the super safe rubber-free Stainless Steel flexible 01-4150 1.5m Kit - BLACK hose with 3/4" UNF connections 01-4106 0.6m Kit - WHITE

Connector Hoses

01-4156

01-4200 600mm Connector Hose 01-4203 300mm Connector Hose 01-4215 1500mm Connector Hose

0.6m Kit - BLACK

90 degree Fill Adapter

01-4210 90 degree Fill Adapter



Used to prevent dangerous over-kinking of Filler hoses in restricted areas: A. Height restriction on top of cylinder Number 2. B. Limited clearance from the back of the Filler.

Turning a single cylinder system into a twin could not be

easier. These Stainless Steel hoses with 3/4" UNF

Cylinder 2 together.

automatically filled.



Filler Hose T-Adapter 01-4212 Filler Hose T-Adapter



Upgrades a Cylinder 1 into a Cylinder 2 without increasing the overall height This may be particularly useful when installing a second 2.7Kg Cylinder.



3 Way Male Fill Adapter 01-4213 3 Way Male Fill Adapter



Designed to fit two Cylinder 1s to a filler or have two fillers - one on either side of the vehicle - going into a single Cylinder 1. This can also be used to extend a filler hose by blanking off one outlet with an 01-4111 Blanking Cap.

Adapters for Gaslow Fill Kits


01-4300 French/Italian Adapter 01-4310 Euro Adapter 01-4305 Spanish Adapter





This French/Italian adapter simply screws into your UK fill point

This Euro adapter simply screws into your UK fill point.



Gaslow Filler with integral UK Bayonet connection with internal screw connection to

take adapters

0

Transfer Kits

01-4110 WHITE 01-4151 BLACK



Gaslow cylinder connected.



01-4111

01-4101 Replacement Filler Cap - WHITE 01-4152 Replacement Filler Cap - BLACK

Blanking Cap

Propane Refillable Adapter



Propane Refillable Adapter 01-4331 Propane Refillable Adapter

Refillable Propane Regulator 01-4337 37mbar Low Pressure Regulator





01-4350 **UK Bayonet Adapter** Euro to UK Bayonet Adapter 01-4351 Euro to French/Italian Adapter 01-4355 French/Italian to UK Bayonet Adapter 01-4360

Bracket for Filling Kit 01-4160 Bracket IMPORTANT





Remote Gas Gauge 01-4030 Remote Gas Gauge




4









connections connects the Gaslow Cylinder 1 and



CYLINDER 1 The centre valve is for filling and has a single inlet which connects directly to the Filler kit or to Cylinder No 2.

CYLINDER 2

The centre valve is for filling and has a double inlet. The side inlet connects directly to the Filler kit and the top connects to Cylinder No 1

Gauge 01-4330

Propane Refillable Adapter Gauge

cylinder.

Fillers

fillers (A).

converts for UK filling (B)


The 01-4355 adapter simply screws on to the filler and converts for French filling.

The 01-4360 is for vans fitted with LPG tanks with French-type fillers. This adapter comes in two pieces (C) and when adjusted and fitted to the French filler , it converts for UK filling(D).

cylinder locker.

With a Bracket, consider using 01-4156 Filler Kit as the shorter hose is normally preferable.(see opposite page "twin 11Kg")

These transfer kits come without a hose and have been designed for customers wishing to transfer their existing Gaslow Refillable System to a new motorhome or caravan and leave the original filling point in place. The kits come with a blanking cap to go onto the old filler to prevent someone inadvertently trying to fill without a





White Replacement Cap for Gaslow Bayonet filler.

This gauge is designed to convert all existing UK Propane gas connections to fit the Gaslow Refillable cylinder.



Black Replacement Cap for Gaslow Bayonet filler



This adapter is designed to convert all existing UK Propane gas connections to fit the Gaslow Refillable



This low pressure regulator is designed to fit directly onto the Gaslow Refillable cylinder

Ideal to run Gas Barbecues, Patio Heaters and other appliances which need a standard 37mbar supply using the Refillable Cylinder.



This UK Bayonet Adapter is NOT required on a Gaslow Filler Kit. It may be needed on some other types of

For imported vans fitted with LPG tanks with Euro-type

The 01-4351 adapter simply screws on to the filler and

This multi-positional bracket can be used to secure the Filling point either to the floor, roof or side walls of your











Simply upgrades your R67 Refillable so you can see the gas contents from inside your vehicle.



Gas Lockers

Gas Locker

01-7010 Small Gas Locker 01-7020 Large Gas Locker



Gaslow offer two sizes of locker - the small, measuring 235mm wide x 270mm deep x 350mm high is suitable for the smaller Campingaz 907 bottles and Gaslow 2.7kg Refillable.

The large, measuring 255mm wide x 290mm deep x 450mm high is designed for Calor 4.5Kg bottles.

Fabricated from mild steel to create a sealed box with a detachable front cover for easy access, it is finished in high quality black powder coating. The gas tight locker is designed with a 55mm lip below the opening to securely contain gas in the event of a leakage and fully complies with BS EN 1942:2002.

Each size comes with bottle strap and drop-out vent to fit your own components or as a complete kit.

Local Cylinder Connection Hose

Local Cylinder Connection Hose. 1.5m 01-4500

Home or abroad and you can't get to a filling point.... now you can use the local cylinders!

Screw the connection aslow Filler and now you can connect any 21.8LH UK or foreign cylinders or adapters...(see Page 9).

When in use, you will be drawing gas through one of your refillables


IMPORTANT - This will NOT transfer the liquid gas to your refillable cylinder. When the added cylinder is empty - so is the refillable you're using





Foreign adapters to access ALL European cylinders (page 9)





Gaslow Direct Fill Cylinder

Now we feel it's time to introduce a direct fill Gaslow cylinder

Gaslow is a name you can depend on with over 35 years experience in developing unique LPG gas sysems. Since 2004, we have fitted many thousands of European approved fixed refillable cylinders.

Now - with more and more customer demand and in excess of 150 owner managed filling stations, we now feel the time is right.

Our New Direct Fill cylinder comes with a FREE regulator to easily connect to your Gas Barbecue or Patio Heater and a FREE Direct Fill Adaptor.



Important Filling advice.

Some people have been trying to fill non-refillable cylinders to save money. This is both illegal and very dangerous resulting in the major petrol companies deciding not to allow any portable cylinders to be filled on their forecourts. This is totally understandable, as they would have to educate all their forecourt staff to be able to identify what should or should not be filled, especially as they could also be held responsible for any overfilled cylinders. For this reason we have not promoted a direct-fill cylinder as you may be affected by this and refused filling. However, we have now contacted smaller owner-managed LPG filling stations who now understand that our system is perfectly safe to fill and are happy to support Gaslow customers. A list of which can be seen on www.gaslowdirect.com

If you want hassle-free filling anywhere... ...upgrade to a fixed cylinder installation

By fixing a permanent filler on the outside of your vehicle your Gaslow will then meet all the requirements of the UKLPG trade association directives so you will be able to fill up anywhere in the UK. Purchase a few filling adaptors and then you will be able to top-up just about anywhere in the world.











CASLOW






The lightweight Gaslow direct-fill cylinder comes with FREE regulator and gauge


Compare the Gaslow 6kg refillable to a 15 litre plastic refillable:

- It fits more cylinder lockers
- It is lighter when full.
 - Gaslow gives an extra 5* years warranty
- It has a contents gauge
 - We include a FREE Propane regulator

*IMPORTANT - Under the TPED standard, composite linders should be re-qualified every 5 years and el cylinders every 10 years.



8





Dutch/German Adapter

Greek/Italian Adapter


USA/UK Adapter

Converts an American OCC1

regulator to fit UK Propane

cylinders

Fits directly on to the outlet of a Gaslow Refillable cylinder preventing dangerous over-stressing and kinking of Stainless Steel regulator hoses in restricted areas. It also fits a the above adapters.



(Shown here fitted to a Jumbo adapte

Gaslow Gauges - Single LP Gas System

01-1605

21.8LH Adapter Gauge - Butane

Adapter Gauge - Propane

21.8LH Adapter Gauge - Propane

01-1605 Designed to fit all 4.5Kg cylinders and all other Gaslow Adapters. To connect, simply screw your **30mbar Caravan Regulator** regulator or hose into the back of the adapter and tighten with a spanner Gaslow 300 System 01-1607 As above. Designed to fit Gaslow Refillables 01-1610

Designed to convert all existing Propane gas systems. Simply screw your regulator or hose


into the back of the adapter and tighten the two together. You now have a low level indicator and leak detector with the added convenience of no longer needing a spanner when

01-1775	30mbar System - 8mm copper
01-1785	30mbar System -10mm copper
01-1674	Easifit adapter

lator failu re's no warning effects are

Where can you find a replacement? It's almost impossible at short notice!.. and then there's the cost!.. ...and what stops it happening again? We quarantee it won't h

> refillables and also an 01-1674 adaptor for propane. Includes a guaranteed FIVE YEAR WARRANTY



1/4" ISO228 Left-hand screw fitting

Wall mounted Regulators - Single LP Gas System pre-2004

21.8LH Butane

01-1635B Reg with G3/8 Female outlet 01-1635B-1 Reg with LP Hose Outlet 01-1635B-2 Reg with 3/8" Compression Outlet 01-1635B-3 Reg with 5/16" Compression Outlet

Propane

01-1650B Reg with G3/8 Female outlet 01-1650B-1 Reg with LP Hose Outlet 01-1650B-2 Reg with 3/8" Compression Outlet 01-1650B-3 Reg with 5/16" Compression Outlet



Regulators - Marine

Regulator Gauge- Propane

30 mbar Marine Regulators 01-3110 Butane with Gauge 01-3100 Butane

Adapter Gauges

28mbar Butane Regulator

01-1728

37mbar Propane Regulator 01-1737

01-1605

01-1607


01-1610



Low pressure regulator specifically designed for the harsh salt environment of sea going craft.to CE0036. It can also be fitted with a Gaslow so you can leak test the complete gas system and it will show when gas is running low



Stainless Steel Propane & Gauge Stainless Steel Propane





Simply screws onto the Marine regulator allowing you to use standard low pressure hose with a worm drive clip.



Wall mounted Regulators - Single LP Gas System





Camping Gas Cylinder with

01-1665 Adaptor

connecting to a cylinder.

7 & 15Kg Butane Cylinders with 01-1670 Clip-On Adaptor

4.5Kg Butane Cylinder DIRECT



W20 Regulator Gauge **Regulator Gauge- Butane**



Gaslow Gauge fitted. This unit simply screws directly on to your 30mbar caravan regulator before your hose



10

Low pressure nozzle


01-3111 low pressure nozzle

01-3115

01-3105

01-1615

01-1620







The Gaslow 300 can be upgraded to a twin manual changeover system (01-1630)



The Gaslow 300 can be upgraded to a twin automatic changeover system (01-1755)

This caravan regulator is a two-stage regulator which can work with both Butane and Propane gas. It has built-in over-pressure protection and switching between different gas cylinders is achieved simply by changing the high pressure hose or adding a Gaslow adapter on to the W20 inlet. It is manufactured to European standard 12867 which is now required for caravans and motorhomes

01-1682 01-1683

Two sizes are available allowing you to take either 8mm or 10mm copper directly from the regulator into the van.

8mm W20 with Test Point 10mm W20 with Test Point

Regulator and bracket to be mounted with a single high-pressure 0.45metre hose which connects to the cylinder. For marine use, the regulator must be connected directly to the copper piping using either the 3/8" or 5/16"

Butane Hose fits Calor 4.5Kg Cylinder -see adapters for other sizes

Propane Hose fits all sizes of Propane Cylinder



Why you need a GASLOW Changeover!

Automatic Changeover

A twin cylinder automatic changeover system designed for ease of operation and peace of mind.

The changeover is operated with both gas cylinders turned ON, first drawing from the 'service' cylinder. When the gas levels run low, the sensing device automatically changes over to the reserve gas cylinder without interrupting the gas flow.

Once changeover has taken place, the indicator shows RED. The internal non-return valve then allows the empty cylinder to be disconnected without switching off your gas supply.

No more disconnecting or re-connnecting of regulators and re-lighting of pilot burners - usually at the most inconvenient time.

Manual Changeover

The Gaslow changeover is a manual twin gas cylinder system providing an easy solution when connecting two gas cylinders together. It enables quick and easy changeover without the hassle of disconnecting the gas cylinders whilst providing all the benefits of the Gaslow gauge.

With both cylinders connected to the system, only one is turned on. When the Gaslow gauge warns of low gas levels, changeover is straightforward.

Simply turn ON the full cylinder and turn OFF the empty one.

The special non-return valve allows the empty gas cylinder to be removed without turning OFF the gas supply.

With a Gaslow - you are in control. You can now decide the most convenient time to change the cylinders.

So make it as easy as possible.

Fit a Gaslow Changeover.



Plastic pointer on Auto changeover points to the cylinder in use (Left). The indicator will show GREEN.



When the Left cylinder empties, the indicator will automatically show RED. This indicates that it has now changed to the spare cylinder.



To change the empty cylinder, rotate the plastic indicator to the cylinder in use.



The window will now change to GREEN. Now replace the empty cylinder and open the cylinder valve ready for use.

No. of Street, or other



Plastic pointer on Auto changeover points to the cylinder in use (Right). The indicator will show GREEN.

Twin LP Gas Systems - for 30mbar caravan regulators

W20 Changeover Gauges 01-1625 Butane standard 01-1630 Propane standard



Butane Front **Propane Front Butane Side**

Propane Side



01-1626

01-1631

01-1627

01-1632

Low Level Indicator

The Gaslow Gauge gives visual warning of low gas levels when gas is being consumed by your appliances.

No worries, gas supply adequate at current rate of use

Auto Changeover Head 01-1755 Butane/Propane



W20 Regulator Adapter (Rt angle) 01-1677 90⁰ Regulator Adapter

the supply.

W20 Blanking Cap 01-1684 Blanking Cap



Remote Appliance Adapter 01-1678 Remote Appliance Adapter

Propane Blanking Cap 01-1679 Propane Blanking Cap

blanking off the loose hose

assembly.





01-1691





12

Designed to create a twin cylinder gas system for new caravans. This unit simply screws on to your 30mbar regulator and allows you to reconnect your existing hose and (with an additional hose) turn your system into a manual changeover with built in leak detection and low-level indicator.

These design configurations are for 30 mbar regulators which are not fitted upright in the middle of a gas locker but are fitted either sideways in the corner, e.g. the (01-1626) or other difficult configurations (01-1627). These special adapters allow you to connect both cylinders before setting off. With Propane this is very helpful as shorter hose lengths make connection difficult in the confined area of the locker.






Green



Yellow Early warning, keep an eve on your gas supply



Simply screw this changeover on to your 30mbar regulator and it works with both Butane and Propane. When gas levels run low, the sensing device automatically changes to the reserve cylinder without interrupting the gas flow. The non-return valve allows disconnection of the empty cylinder without disrupting





Designed to blank off a manual or automatic changeover if connecting only one cylinder



Simply screws onto the W20 end of a high pressure hose allowing the cylinder to stay in the locker and run a remote propane appliance fitted with a standard propane regulator. e.g. a gas generator or barbecue.

Ideal for owners of Gaslow Refillables. It is recommended that you use 01-6036-SS Gaslow Stainless Steel hose

Allows you to use a Manual or Automatic propane changeover with only one cylinder connected by





Protects the regulator from dirty gas. The head can be rotated for easier installation in confined areas.





Replacement Washers / Spanner








Twin LP Gas Systems - pre 2004

Switch 2 01-5050 Switch 2



For pre-2004 models, this is an alternative twin gas cylinder connection system which uses your existing regulators.

It is designed for the low-pressure side of your gas system after your regulators. The two supply inlets are controlled by a two-way tap and can use either type of LP gas - one side can be Propane, the other side Butane. Switch-2 makes changeover easy and allows the empty cylinder to be removed without switching off the supply. It is supplied with 3 hose clips and is fitted with a mounting bracket.



Manual Changeovers

01-1645 Butane 28mbar 01-1650 Propane 37mbar



Designed for twin cylinder Propane systems conforming to the original British Standard, it is a manual changeover regulator complete with an integral mounting bracket. Comes standard with a hose nozzle but optional 5/16" and 3/8" compression fittings are available.

High pressure hoses are available seperately.



Auto Changeover 37mbar Propane

01-1655 + Low pressure nozzle + 3/8" compression 01-1655-1 01-1655-2 + 5/16" compression



Designed for twin cylinder Propane systems conforming to the original British Standard, it is an automatic changeover regulator complete with an integral mounting bracket. Comes standard with a hose nozzle but optional 5/16" and 3/8" compression fittings are available

High pressure hoses are available separately.



Auto Changeovers -30mbar

01-1655-ENR Propane 30mbar




motorhomes and for imported vans which need a 30mbar regulator. High pressure hoses are available seperately One of a range of 4 optional outlets need to be specified.

Designed to EN12864 for new caravans and

01-1680 Low pressure nozzle 01-1681 1/4" left-hand German Fitting 8mm Compression Fitting









Examples of 30mbar Regulator upgrades

Due to space restrictions, some manufacturers fit the 30mbar regulators in positions that make it slightly more complicated to upgrade and below are three typical examples with their options.





Truma Regulator already supplied with a 90 degree elbow fitted close to a reinforcing strut on the left



Option 1 Fit a 01-1631 and have both cylinders connected



Option 2 Loosen and rotate the pre fitted elbow 30 degrees -Fit an 01-1755 automatic changeover head. Notice we have used a 01-1677 on the right outlet due to the restriction of the back wall

Option 1 Fit a 01-1630 and have both cylinders connected



Option 2 Fit an 01-1755 automatic changeover head.

Auto Changeovers- 50mbar 01-1755-50 Propane 50mbar Propane Reg 01-1750

14



01-1682 01-1683 10mm Compression Fitting

Designed for older caravans and motorhomes imported from the continent which need a 50mbar regulator and would like to have the benefits of an automatic changeover. High pressure hoses are available separately.



The Basic Installation

The majority of 30mbar regulators are positioned centrally in the locker . making an upgrade straightforward.



Truma Regulator already supplied with a 90 degree elbow fitted on its side close to a reinforcing strut





Typical configuration with Regulator in top right and inlet facing you.



Option 1 Fit a 01-1631 and have both cylinders connected



Option 2 Fit an 01-1755 automatic changeover head using a 01-1677 right angled adaptor. Height has been lowered so use Stainless Steel 01-6050-SS.